WEST TRITON

A Baker Marine 'Pacific Class', 375 fsw rated, 15k BOP jack-up. It is a modern rig which enjoys the improved safety, operational efficiencies and equipment benefits of the latest generation of drilling units. The rig features higher storage capacities in terms of space, weights and volumes for bulks, liquids and general cargo compared to older rigs. The rig's safety case was approved in line with Australian legislation, National Offshore Petroleum Safety Authority (NOPSA) Safety Case Guidelines and the IADC Case Guidelines for Mobile Offshore Drilling Units. The rig has also received recognition from NOPSA for its best in class safety performance throughout 2008 in Australia.

Further information Tel: +47 5130 9000 www.seadrill.com

GENERAL

Design	BMC Pacific 375
Built/year	PPL Shipyard, Singapore / 2007
Jack-up type	Independent leg jack-up
Major upgrades	Nil
Flag	Panama
Classification	ABS
Class notations	✠A1 Self Elevating Drilling Unit

MAIN DIMENSIONS/TECHNICAL

Length x breadth	236 ft x 224 ft
Transit Draft	19.5 ft
Leg length	506 ft
Usable leg below hull	435 ft
Leg spacing	155,2 ft transverse 145.3 ft longitudinal
Spudcan diameter	55.4 ft
Design water depth	375 ft
Min. water depth	50 ft
Drilling depth	30,000 ft
Drilling envelope	70 ft x 30 ft
Variable load	7,500 kips
Helideck	S61N
Helideck compliance	CAP437
Accommodation	115 (100 in Aust/NZ)

STORAGE CAPACITIES

Fuel	3900
Drill water	21,403 bbls
Potable water	4,000 bbls
Liquid mud	4,196 bbls
Base oil	1,145 bbls
Brine	1,310 bbls
Barite/Bentonite	5,827 cu ft
Cement	5,827 cuft
Sack storage	5,000 sacks

POWER

Main engines	5 x Cat 3516B
Main generators	5 x Baylor @ 1,720 kW
Total power	10,750 HP
Emergency power	1 x Cat3508TA x 1,008 HP

DRILLING EQUIPMENT

Derrick	35 ft x 35 ft x 160 ft
Hookload	1,500 kips
Drawworks	NOV Dreco D3,000UE AC 3 x 1,350 Cont.
Racking capacity	330 Stands
Top drive	NOV / Hydralift Power Swivel 750-E-AC 65,450 ft/lbs cont torque
Pipe handling	Hydraflift HPS 750-EAC
Iron roughneck	Hydra Tong PD-MPT
Rotary table	NOV D-495, 49.5"
Power slips	B&V PS 500
Autodriller	Yes
Driller instrumentation	NOV Hitec Cyberbase

TUBULARS

Drill pipe	5-1/2" DP

WELL CONTROL

BOP	Hydril GX 18-3/4" 10k ABOP Hydril 18 3/4" 15k 2xDRAM
Diverter	49.5" KFDJ 500 psi
C&K manifold	15k psi RB Pipetech
BOP hoist	2 x Ingersoll Rand hoists x 55 st
Conductor tensioner	500 kips

MUD SYSTEM

Mud pumps	3 x NOV 14-P-220
Pressure rating	7,500 psi
Shale shakers	4 x Brandt VSM300

LIFTING EQUIPMENT

Deck crane	3 x BMC 2250/1600/900
Main block rating	(2250) 55 st @ 25 ft / 17 st @ 120 ft (1600) 45 st @ 25 ft / 8.7 st @ 100 ft (900) 25 st @ 20 ft / 7.8 st @ 100 ft
Whip line Rating	5.5 st

OFFLINE ACTIVITY CAPABILITY

Nil

OTHER FEATURES

Helo refuelling system, Dual Mud System, Coring Caisson